Chisel Paste

e Epiroc

CHISEL PASTE

Epiroc Chisel Paste is a specially designed grease used for lubricating the wear bushings of hydraulic breakers. It prevents cold welding in the area of the bushings.

Standard greases (i.e, those used on excavator bearings) are not designed

for the high temperatures that result from the friction between the working tool, bushings and retainer bars when the hydraulic breaker is in operation. They liquefy and disappear. Without greasing, the parts involved in the friction will suffer from accelerated wear.

United in performance. Inspired by innovation.



epiroc.com

 Excellent performance at high temperature 			
🕂 Tailor made for breakers			
🕂 Less wear	Lubricate at regular	2	
🕂 Long tool life	intervals. Do not over lubricate. Reposition		tu _n ,
🕂 Reduced cost of operation	tool at regular intervals to avoid overheating.		V
Features	Benefits		

realules	Denents
Excellent EP (Extreme Pressure) properties and good release effect.	 The solids content (specially the metal content) acts as a ball bearing, resulting in considerably less wear on the bushings and working tools.
Temperature range from -20°C to +1100°C/-4°F to +2012°F	 You can work with your breaker long, continuous periods, even in warmer climates, with the Chisel Paste keeping its protective properties.
Age-resistant composition	 No need to replace grease cartridges after long idle periods of the breaker. Chisel Paste keeps their protective properties, even when breaker is used occasionally.
 Epiroc Chisel Paste is available on Contilube II[™] and Contilube[™] II Micro cartridges. They can be refilled using grease containers of 18 kg and 45 kg (39.68 lb and 99.2 lb). 	 Fast and clean change of cartridges on the Contilube™ II lubrication system, when you run out of Chisel Paste.

Chisel paste

Cartri	dges/Buckets	Use		
Î	150g/5.3oz cartridges for ContiLube™ II Micro	For automatic lubrication in Epiroc breakers fitted with ContiLube™ II Micro. Refillable.		
	500g/17.6oz cartridges for ContiLube™ II	For automatic lubrication in Epiroc breakers fitted with ContiLube™ II and manual greasing with a grease gun. Refillable.		
Ī	400g/14oz cartridges	For manual greasing with a grease gun in all breakers, including handheld hydraulics, from all brands.	the l Office	
	18kg/39.68 lbs buckets	For manual greasing with a grease gun or for refill of ContiLube® II cartridges.		
	45kg/99.2 lbs buckets	For manual greasing with a grease gun or for refill of ContiLube® II cartridges.		

epiroc.com

9864 0014 01 2021-06 Essen, Germany. Legal Notice © Copyright 2021, Epiroc Construction Tools GmbH, Essen, Germany. All product names in this publication are trademarks of Epiroc. Consult your Epiroc Customer Center for specific information.